



MODULAR
SERVICES COMPANY

SPECIFICATIONS

BED DOCKER™



The Modular Services Bed Docker™ provides a “docking” location for the patient bed with electrical devices on each side. These devices will be as shown on the project drawings.

Services are segregated into compartments and all pre-installed devices are pre-wired to service termination locations, ready for connection to the incoming services being fed from the building wall behind.

The Bed Docker module incorporates 16-gauge steel housing for installation of the electrical devices. This housing is trimmed with a single piece, high-impact Kydex® cover. The standard color of the Kydex® cover is “Surf”.



MODULAR
SERVICES COMPANY

109 NE 38th St. • Oklahoma City, OK 73105
Tel: 800.687.0938 • Fax: 405.528.0368
www.headwalls.com • info@headwalls.com